



THE HARYANA BUILDING AND OTHER CONSTRUCTION WORKERS WELFARE BOARD

1st Floor, 30-Bays Building, Sector 17-B, Chandigarh. Tel: 0172-2770081, 2701337

TENDER NOTICE

Sealed quotations/proposal, for the below mentioned work in **Gurgaon, Faridabad, Sonapat, Hissar, Panipat & Yamuna Nagar Districts**, are invited from interested Agencies/individuals:-

Sr. No.	Name of Work	Requirements
1.	Mobile Toilets	A) To establish the ten seaters mobile toilets as per specifications mentioned on our website www. Hrylabour.org . B) To provide round the clock services/facilities of mobile toilets for a period of two years alongwith sweeper for construction workers residing in clusters at various construction sites. The agency will also arrange for water, electricity & disposal of sludge & sewage.
2.	Mobile Crèches	A) To establish removable/foldable crèches (with minimum total covering area= 500 Sq.ft) having one hall, kitchen and bathroom for the accommodation of 30 children/infants as per specifications mentioned on our website www. Hrylabour.org . B) To provide services/facilities to run the crèche with one woman trained in the care of children and infants, one helper, one sweeper and other items like feed, sleeping beds, cradles and toys etc. for siblings of the construction workers at construction sites. The agency will also arrange for drinking water, utensils for cooking, fans & Generator, electricity & disposal of sludge & sewage.

Last date for submission of quotation/proposal will be 09.09.2010 upto 11 A.M. & the same shall be opened on the same day at 3 P.M. in the office the Board. For any other information, if any, the office of the Board can be contacted on Telephone (phone no. 0172-2701337) or in-person.

Other terms & conditions/requirements alongwith specification of construction of mobile toilet & removable crèche can be seen/downloaded from our website www.hrylabour.gov.in

SECRETARY
THE HARYANA BUILDING AND OTHER
CONSTRUCTION WORKERS WELFARE
BOARD.

Specification of Construction of Mobile Crèche:

SPECIFICATIONS:

- a) Having area 500 sq. ft.
- b) One Toilet having size 4' X 4'
- c) Main Door having size of 213.36 cm X 121.92 cm
- d) Side Door, Toilet Door & kitchen Door having size of 213.36cm X 60.96 cm.
- e) Two window having size of 121.92 cm X 91.44 cm.
- f) Temporary Foundation/ cement Concrete flooring area 500 sq.ft.
- g) Outer Metal frame 50mm X 50mm sq. M.S. Tube & 50 mm X25 mm M.S. Tube
- h) Truss of round tube 32mm dia.
- I) Panel should be 12mm thick plastic panel both side of the wall.
- j) Electrical fittings: Two wall fans, Two Tube lights
- k) Water connection with tank capacity 500 liters
- l) Bathroom fittings
- m) Septic tank

ADDITIONAL WORKS

- A) Carpet 320 sq. ft.
- B) Play ground 800 sq. ft.
- C) Boundary wall.
- D) One 6 feet water cooler.
- E) Playing equipments.
- F) Grass, tree & plants.
- G) 4 feet wide road.
- H) One Double Bed, One table, two chairs, water filter.

Terms & Condition

- 1. Service charges for running the crèche as per specification will be paid on monthly basis.
- 2. Tax will be deducted at source as per rules applicable.
- 3. Security deposit @ 5% will be withheld by the Board from the amount payable in respect of constructed work, which will be released after two months of successful running of the crèche.
- 4. It will be the responsibility of party to provide the facility of drinking Water & Electricity.

Specification of Construction of 10 Seaters Mobile Toilet (Back To Back):

GENERAL SPECIFICATIONS:

Size: 15 feet X 6 feet with 7 feet height

Passage Area: 15 feet X 3 feet for each side

Water facilities with double water tank

Electricity fitting

TECHNICAL SPECIFICATION:

Base: Truck chassis

Floor Base: 5 mm thick M.S.Sheet

Structure: 40x40 mm M.S. tube,
Wall: 40 mm insulated FRP wall,
Roof: 6 mm thick FRP roof,
Door: 40 mm insulated FRP door
Disposal Tank: 10 feet X 3 feet dia movable disposal tank
False ceiling with electrical fittings
3 feet height hand railing at passage area

Terms & Condition

1. Payment will be released after successful completion of construction work.
2. Service charges for running the toilet as per specification will be paid on monthly basis.
3. Tax will be deducted at source as per rules applicable.
4. Security deposit @ 5% will be withheld by the Board from the amount payable in respect of constructed work, which will be released after two months of successful running of the Mobile Toilet.
5. It will be the responsibility of party to provide the facility of drinking Water & Electricity and disposal of sludge and sewage at its own part.

TENDER DOCUMENT

10 Seaters Mobile Toilets (Back to Back)

Name of Firm with Previous experience	
(a) Rate for establishment of one Mobile Toilet having 10 seater (back to back) as per specification	
(b) Service charge Per month for running the mobile toilet such as Sweeper, Water, electricity, disposal of sludge etc.	

TENDER DOCUMENT

Mobile Crèche

Name of Firm with previous experince	
(a) Rate for Establishment of one removable crèche as per specification	
(b) Service charge for running the removable crèches with one woman trained in the care of children & infants, one helper, one sweeper and other items like feed, sleeping beds, cradles and toys etc. for sibling of the construction workers.	